PSZ 19:16 (Pind. 1/07)

UNIVERSITI TEKNOLOGI MALAYSIA

DECLARATION OF THESIS / UNDERGRADUATE PROJECT PAPER AND COPYRIGHT		
KONG	LING KAI	
22 MAY	1963	
Date of birth :		
Title : <u>PERFOR</u>	MANCE OF MECHANICAL COUPLER FOR THE CONNECTION	
OF PRE	CAST CONCRETE WALL PANELS	
2008/20	009	
I declare that this thesis is clas	sified as :	
CONFIDENTIAL	(Contains confidential information under the Official Secret Act 1972)*	
	(Contains restricted information as specified by the organization where research was done)*	
	I agree that my thesis to be published as online open access (full text)	
I acknowledged that Universi	ti Teknologi Malaysia reserves the right as follows:	
 The thesis is the proper The Library of Universities 	ty of Universiti Teknologi Malaysia. Teknologi Malaysia has the right to make copies for the purpose	
3. The Library has the righ	nt to make copies of the thesis for academic exchange.	
	Certified by :	
SIGNATURE 630522-10-7849	SIGNATURE OF SUPERVISOR PROF MADYA DR AHMAD BAHARRUDIN	
(NEW IC NO. /PASSPOR	NO.) NAME OF SUPERVISOR	
Date : 25 NOVEMBER 200	B Date : 25 NOVEMBER2008	

NOTES : * If the thesis is CONFIDENTAL or RESTRICTED, please attach with the letter from the organization with period and reasons for confidentiality or restriction.



RUJUKAN KAMI (OUR REF.) :

RUJUKAN TUANI (YOUR REF.) :

25 November, 2008

KEPADA SESIAPA YANG BERKENAAN

Saudara,

PROJEK SARJANA KATEGORI TERHAD

Tajuk Projek : Performance of Mechanical Coupler for the Connection of Precast Concrete Wall Panels

Pelajar : Kong Ling Kai

Merujuk perkara di atas, projek penyelidikan yang dijalankan oleh pelajar adalah sebahagian daripada projek penyelidikan di antara Construction Research Institute of Malaysia (CREAM) dan Universiti Teknologi Malaysia, Vot RMC-UTM 73713.

Produk penyelidikan yang dilaporkan berpontensi untuk di'patent'kan. Oleh itu laporan projek sarjana ini adalah dikategorikan sebagai TERHAD dan tidak dibenarkan untuk dibaca, diedar atau dibuat salinan oleh mana-mana pihak bagi membolehkan produk penyelidikan yang dilaporkan dapat di 'patent'kan.

Tempoh terhad adalah 2 tahun iaitu dari 25.11.08 sehingga 25.11.10.

Kerjasama dari pihak saudara didahului dengan ucapan terima kasih.

BERKHIDMAT UNTUK NEGARA

Yang Benar,

PROF. MADYA DR. AHMAD BAHARUDDIN BIN ABD. RAHMAN Ketua Projek Penyelidikan Fakulti Kejuruteraan Awam Universiti Teknologi Malaysia Skudai, Johor (🕾 : 07-5531598, 013-7305127) "I hereby declare I have read this thesis and in my opinion this thesis is sufficient in terms of scope and quality for the award of the degree of Master of Engineering (Civil - Structure)"

Signature	:	
Name of Supervisor	:	Associate Professor Dr. Ahmad
		Baharuddin bin Abd Rahman
Date	:	25 November 2008
Date	:	25 November 2008

PERFORMANCE OF MECHANICAL COUPLER FOR CONNECTION OF PRECAST CONCRETE WALL PANELS

KONG LING KAI

A project report submitted in partial fulfillment of the requirements for the award of the degree of Master of Engineering (Civil – Structure)

> Faculty of Civil Engineering University Technology of Malaysia

> > NOVEMBER, 2008

I declare that this thesis entitled "Performance of mechanical coupler for connection of precast concrete wall panels" is a result of my own research except as cited in the references. The thesis has not been accepted for any degree and is not concurrently submitted in candidature of any other degree.

Signature	:	
Name	:	KONG LING KAI
Date	:	<u>25 November 2008</u>

Dedicated to my beloved wife and daughters

ACKNOWLEDGEMENTS

For my wife, thanks for encouraging and supporting me through thick and thin. Thank you for being with me and motivate me whenever I need it. Without you I will not be able to complete my master degree.

I would also like to express my utmost appreciation to Ir. Haji Zamani Adam and Mr Soo Peng Kwai for giving me moral as well as financial support for the whole duration of my studies.

Many thanks also to my supervisor, Prof. Madya Dr. Ahmad Baharuddin bin Abd Rahman for spending his time helping me to solve the problems that I had encountered during my thesis preparation. Thank you for your supervision and guidance and for being a good supervisor.

To all my course mates, thank you for the cooperation and encouragement. I sincerely wish you all a bright and rewarding future.

ABSTRACT

In a precast wall-slab system, the wall connections played an important role in ensuring structural integrity and safety of the building. The connections are also required to cater for the provision of structural ties to enhance the building's robustness to overcome progressive collapse. In normal practice, continuity between upper precast walls and lower precast walls are carried out by lapping the reinforcement bars. This practice often caused congestion in the connection and may create honeycomb or voids in concrete if precaution is not taken during concreting. The use of mechanical couplers to replace the reinforcements lapping is a logical solution because these mechanical couplers do not occupied long lap length, easy to install and avoid bar congestion in the wall connection. However, these mechanical couplers are expansive and not many are available in the local market. In this paper, we have carried out tensile tests on ten numbers of specially designed grout filled mechanical couplers to evaluate their performances based on tensile capacity and failure patterns. These specimens were of the same make and specification but they vary in terms of type of grout material used and bolt configurations. The tests results show that higher grout strength produces better anchorage bond and subsequently higher tensile strength for the coupler. The test results also show that providing bolts on the coupler enhanced the tensile strength because these bolts act as shear keys which interlocked with the grout. The optimum arrangement of bolts shall be two bolts in a same plane. Overall all the couplers tested failed to achieve the required strength but nevertheless, the information gathered on the understandings of the causes of failure, influences of grout and bolt configurations will provide essential groundwork for future research.

ABSTRAK

Di dalam pembinaan sistem pasang siap dinding-papak, sambungan memainkan peranan yang penting untuk memastikan integriti struktur dan keselamatan bangunan adalah kukuh. Sambungan juga perlu direkabentuk untuk menambahkan kekukuhan bangunan dalam menangani keruntuhan progresif. Kebiasaannya, kesinambungan antara dinding pasang siap atas dan dinding pasang siap bawah disambungkan dengan kaedah tindihan pada tetulang besi. Tindihan pada tetulang besi lazimnya menyebabkan kesesakan dalam sambungan dan mungkin akan menyebabkan konkrit berongga. Penggunaan penyambung mekanikal pada tetulang besi adalah satu penyelesaian yang baik kerana penyambung mekanikal tidak mempunyai tindihan yang panjang, mudah dipasang serta tidak membawa kesesakan pada sambungan. Akan tetapi, harga penyambung mekanikal dalam pasaran adalah mahal dan tidak mudah diperolehi. Di dalam kertas kerja ini, ujian tegangan akan dijalankan keatas sepuluh spesimen yang direkabentuk khas untuk menilai kekuatan tegangan dan corak kegagalannya. Penyambung mekanikal ini adalah dibuat daripada bahan dan spesifikasi yang sama tetapi berbeza dari segi penggunaan grout simen dan susunan bolt. Keputusan ujian mendapati bahawa kekuatan grout simen mempengaruhi kapasiti tegangan penyambung. Keputusan ujian juga menunjukkan bahawa dengan menggunakan bolt pada penyambung dapat menambahkan kapasiti keupayaan penyambung kerana bolt berfungsi sebagai kekunci ricih yang mengunc kegelnciran grout. Penyusunan bolt yang optima adalah dua bolt pada satah yang sama. Secara keseluruhan kesemua penyambung gagal mencapai kekuatan yang diperlukan tetapi maklumat mengenai corak kegagalan, kesan kekuatan simen grout pada coupler dan susunan bolt yang optima dapat memberikan informasi yang penting untuk kajian seterusnya.

TABLE OF CONTENTS

TITLE

CHAPTER

	DEC	CLARATION	ii
	DED	DICATION	iv
	ACK	KNOWLEDGEMENT	v
	ABS	TRACT	vi
	ABS	TRAK	vii
	TAB	BLE OF CONTENTS	X
	LIST	Г OF TABLES	xiv
	LIST	F OF FIGURES	XV
	LIST	Γ OF SYMBOLS	xix
CHAPTER 1	INT	RODUCTION	1
	1.1	Introduction	1
	1.2	Scope & Objectives	2
	1.3	Problem statement	3
	1.4	Expected findings	3
CHAPTER 2	LIT	ERATURE REVIEW	5
	2.1	Introduction	5

PAGE

2.2	Structu	ral Concept for Precast Concrete Systems	6
2.3	Wall-S	lab Frame Structural Systems	7
2.4	Progre	ssive Collapse	8
	2.4.1	Rona Point Apartment Collapse	8
	2.4.2	Provision in BS8110 on Progressive	10
		Collapse.	
2.5	Design	of ties in precast concrete wall system	12
2.6	Conne	ctions for Precast Walls	15
2.7	Types	of horizontal connection for wall panels	16
2.8	Mecha	nical Couplers or Splice Connectors	18
2.9	Types	of Mechanical Coupler Connectors	20
	2.9.1	Sleeve-Swaged Mechanical Coupler	21
	2.9.2	Sleeve-Threaded Bar Mechanical Coupler	22
	2.9.3	Sleeve Tapered Thread Mechanical Coupler	23
	2.9.4	Sleeve-Filler Metal Mechanical Coupler	24
	2.9.5	Sleeve-Filler Grout Mechanical Coupler	25
	2.9.6	Sleeve-Lock Shear Bolts Mechanical	26
		Coupler	
	2.9.7	Wedge-Thru Sleeve (Mechanical Lap	27
		Splicing)	
2.10	Ancho	rage Bond	27
	2.10.1	Lap Splices	30
	2.10.2	Confinement of Splitting Stresses	30
	2.10.3	Effects of Concrete Properties	33
2.11	Design	provision for calculating development	34
	or splic	ce length	
	2.11.1	Orangun, Jirsa and Breen	34
	2.11.2	Eshafani and Rangan	35
	2.11.3	Darwin et al	36
	2.11.4	Zuo and Darwin	37
	2.11.5	ACI 318	38

	2.11.6 ACI 408.3	39
2.12	Shear Cone Theory in Headed Bars Anchorage	41
	2.12.1 Concrete Cone Breakout	42
	2.11.2 Anchorage Failure Load Estimate	44

CHAPTER 3 METHODOLOGY 46

3.1 Introduction 46 Experimental Test Set Up 3.2 48 Preparation of Test Specimens 3.3 49 3.3.1 Cement Grout for mechanical coupler 50 3.3.2 High yield reinforcing bars 50 3.3.3 Strain gauges 51 3.3.4 Proposed mechanical couplers 52 3.3.4.1 Specimens A1 and B1 53 3.3.4.2 Specimens A2 and B2 54 3.3.4.1 Specimens A3 and B3 55 Specimens A4 and B4 3.3.4.1 56 Specimens A5 and B5 3.3.4.1 57

CHAPTER 4 TEST RESULTS

Introduction	58
Test cube results	59
Tensile test on high yield 16 mm diameters bar	60
Specimens' Test Results	61
4.4.1 Test Results for Specimen A1	62
4.4.2 Test Results for Specimen A2	64
4.4.3 Test Results for Specimen A3	66
4.4.4 Test Results for Specimen A4	68
4.4.5 Test Results for Specimen A5	70
	IntroductionTest cube resultsTensile test on high yield 16 mm diameters barSpecimens' Test Results4.4.1Test Results for Specimen A14.4.2Test Results for Specimen A24.4.3Test Results for Specimen A34.4.4Test Results for Specimen A44.4.5Test Results for Specimen A5

58

4.4.6	Test Results for Specimen B1	72

- 4.4.7Test Results for Specimen B2744.4.2Test Results for Specimen B274
- 4.4.8Test Results for Specimen B376
- 4.4.9Test Results for Specimen B478
- 4.4.10 Test Results for Specimen B580

CHAPTER 5DISCUSSION OF RESULTS82

5.1	Introduction	82
5.2	Summary of Test Results	83
5.3	Failure patterns of Test Specimens	86
	5.3.1 Slippage and pullout of reinforcement	87
	from the Coupler	
	5.3.2 Pullout of Grout from the Coupler	88
5.4	The effects of Grout strength towards the	89
	tensile resistance of Coupler	
5.5	The effects of Bolts towards the tensile	91
	resistance of Coupler	

CHAPTER 6 CONCLUSIONS AND RECOMMENDATIONS 93

6.1	Introduction	93
6.2	Conclusions	93
6.3	Recommendations	94

REFERENCES

97

LIST OF TABLES

TABLE NO.	TITLE	PAGE
4.1	Cube Test results for cement Grout	59
5.1	Summary of Tensile Test results for Specimens A1-A5	83
5.2	Summary of Tensile Test results for Specimens B1-B5	84

LIST OF FIGURES

FIGURE NO.

TITLE

PAGE

2.1	Wall-Slab Frame Precast System	7
2.2	Ronan Point Building after 16 May 1968 collapse	9
2.3	Schematic of Ronan Point Building collapse	9
2.4	Extracts from BS8110: Part 1: 1997 on Robustness	10
2.5	Location of Structural Ties in Precast Skeletal Structure	11
2.6	Location of Transverse and Vertical Ties in Precast Wall System	12
2.7	Elevation view showing the location of Transverse and Vertical	13
	ties in Precast Wall System.	
2.8	The effects of Structural Ties in the Wall-Slab System will prevent	14
	Progressive Collapse in the event of localized failure.	
2.9	Exterior Forces and Joint Forces System	15
2.10	Behavior of a Precast Wall subjected to lateral force.	16
2.11	Different Types of Horizontal Joints	17
2.12	Isolated Connection in Wall Panels	17
2.13	Comparison of Splice Lapping and Mechanical Coupler	19
2.14	Congestion of Reinforcing bars can be avoided if Mechanical	20
	Couplers are used.	
2.15	Cold Swaged Method	21
2.16	Sleeve Swaged Coupler produced by BarSplice Product Inc.	21
2.17	Sleeve – Threaded Coupler produced by BarSplice Products Inc.	22

2.18	Sleeve-Threaded Coupler from Dayton Superior Corp.	22				
2.19	Sleeve Tapered Thread Coupler from Erico International					
2.20	Erico Lenton A-2 (Sleeve Tapered Thread Coupler)	23				
2.21	Sleeve –Filler Metal Coupler by Erico International.					
2.22	NMB Splice Sleeve from by Splice Sleeve North America Inc.	25				
2.23	Sleeve-Lock Shear Bolts Coupler by BarSplice Products Inc.	26				
2.24	Cross Section of a Sleeve-Lock Shear Bolts Coupler	26				
2.25	Wedge Thru Sleeve Coupler by Erico Inc.	27				
2.26	Simple Concept of Bond Stresses	28				
2.27	Bond and Splitting Components of Rib Bearing Stresses	29				
2.28	Types of Splitting Crack Failure	29				
2.29	Splitting Cracks in a Lap Splice joint.	30				
2.30	Example of Active Confinement	31				
2.31	Confinement Steel in the vicinity of a Splitting Crack	32				
2.32	Crack widths of Splitting Crack	32				
2.33	Influence of poor concrete placement	33				
2.34	Anchorage of a headed bar	41				
2.35	Plate Head welded to reinforcing bar	41				
2.36	The Xtender Coupler System that utilized the Forged Heads	42				
2.37	Concrete Failure Cone for Headed bar	42				
2.38	ACI assumptions on shapes of Concrete Failure Cone.	43				
2.39	Formula to calculate Single Anchors Failure Load	44				
2.40	Design Chart for Headed Studs Cone Failure Load	45				
3.1	Flowchart of Methodology	47				
3.2	Tensile Test Set Up	48				
3.3	Test Specimens grouted with cement grout	49				
3.4	Strain Gauges	51				
3.5	Strain gauges attached to the rebars and mechanical couplers	51				
3.6	Typical Section of specially designed mechanical coupler	52				
3.7	Specimen A1 and B1 Coupler details	53				

3.8	Photograph of Specimen A1 and B1	53
3.9	Specimen A2 and B2 Coupler details	54
3.10	Photograph of Specimen A2 and B2	54
3.11	Specimen A3 and B3 Coupler details	55
3.12	Photograph of Specimen A3 and B3	55
3.13	Specimen A4 and B4 Coupler details	56
3.14	Photograph of Specimen A4 and B4	56
3.15	Specimen A5 and B5 Coupler details	57
3.16	Photograph of Specimen A5 and B5	57
4.1	Stress vs Strain graph for T16 bars	60
4.2	Load vs Deformation graph for T16 bar	61
4.3	Failure mode of Specimen A1	62
4.4	Stress vs Strain diagram for Specimen A1	63
4.5	Load vs Deformation graph for Specimen A1	63
4.6	Failure mode of Specimen A2	64
4.7	Stress vs Strain diagram for Specimen A2	65
4.8	Load vs Deformation graph for Specimen A2	65
4.9	Failure mode of Specimen A3	66
4.10	Stress vs Strain diagram for Specimen A3	67
4.11	Load vs Deformation graph for Specimen A3	67
4.12	Failure mode of Specimen A4	68
4.13	Stress vs Strain diagram for Specimen A4	69
4.14	Load vs Deformation graph for Specimen A4	69
4.15	Failure mode of Specimen A5	70
4.16	Stress vs Strain diagram for Specimen A5	71
4.17	Load vs Deformation graph for Specimen A5	71
4.18	Failure mode of Specimen B1	72
4.19	Stress vs Strain diagram for Specimen B1	73
4.20	Load vs Deformation graph for Specimen B1	73
4.21	Failure mode of Specimen B2	74

4.22	Stress vs Strain diagram for Specimen B2	75				
4.23	Load vs Deformation graph for SpecimenB2	75				
4.24	Failure mode of Specimen B3	76				
4.25	Stress vs Strain diagram for Specimen B3	77				
4.26	Load vs Deformation graph for Specimen B3					
4.27	Failure mode of Specimen B4					
4.28	Stress vs Strain diagram for Specimen B4	79				
4.29	Load vs Deformation graph for Specimen B4	79				
4.30	Failure mode of Specimen B5	80				
4.31	Stress vs Strain diagram for Specimen B5	81				
4.32	Load vs Deformation graph for Specimen B5	81				
5.1	Test results for Specimens A1 to A5	85				
5.2	Test results for Specimens B1 to B5	86				
5.3	Slippage and pullout of reinforcement	88				
5.4	Pullout of grout occurred at the top portion of reinforcement	89				
5.5	Comparison between specimens grouted with SIKA and OPC grout	90				
5.6	Specimen 2 x (2x2) configuration					
5.7	Cross section of Coupler	92				

6.1	New coupler design based on experimental finding.	95
-----	---	----

xvii

LIST OF SYMBOLS

A_b	-	area of bar being developed or spliced							
	-	area of largest bar being developed or spliced (CEB-FIP 1990)							
A_{tr}	-	area of each stirrup or tie crossing the potential plane of splitting							
		adjacent to the reinforcement being developed, spliced or anchored.							
c	-	spacing or cover dimension ($c_{min} + d_b/2$)							
c _b	-	bottom concrete cover for reinforcing bars being developed or spliced							
c _{max}	-	maximum (c_b, c_s)							
c _{med}	-	median $(c_{so},c_b,c_{si}+d_b/2)$ that is, middle value (Esfahani and Rangan)							
c_{min}	-	minimum cover used in expressions for the bond strength of bars not							
		not confined by transverse reinforcement.							
	-	minimum $(c_{so},c_b,c_{si}+d_b/2)$ ((Esfahani and Rangan)							
	-	smaller of minimum concrete cover or $\frac{1}{2}$ of the clear spacing between							
		bars							
cs	-	minimum of (side concrete cover, ¹ / ₂ fo the bar clear spacing 0.25in							
c _{si}	-	1/2 of the bar clear spacing							
c _{so}	-	side concrete cover for reinforcing bar							
d_b	-	diameter of bar							
Ec	-	modulus of elasticity for concrete							
f_c	-	stress in concrete							
$f_{c'}$	-	concrete compressive strength based on 6x12in. (150x300mm) cylinders							
	-	specified concrete strength of concrete							
f_{ct}	-	average splitting tensile strength of concrete							

xviii

f_s	-	stress in reinforcing bar
f_y	-	yield strength of steel bar being developed or spliced
f_{yt}	-	yield strength of transverse reinforcement
l_d	-	development or splice length
l _{d, min}	-	minimum development length
$l_{s,min}$	-	minimum splice length
n	-	number of bars being developed or spliced
Ν	-	the number of transverse stirrups, or ties, within the development or
		splice length.
r	-	constant used in expressions for bond strength of bars not confined by
		transverse reinforcement; a function of Rr
	-	3 for conventional reinforcement $9Rr = 0.07$) (Esfahani and Rangan)
Rr	-	relative rib area of the reinforcement
S	-	spacing of transverse reinforcement
s _r	-	average spacing of deformations on reinforcing bar
t _d	-	term representing the effect of bar size on Ts
	-	$0.72d_b + 0.28$, $(0.028d_b + 0.28)^*$ (Darwin et al. 1996a,b)
	-	$0.78d_b + 0.22$, $(0.03d_b + 0.22)^*$ (Zuo and Darwin 1998,2000)
t _r	-	term representing the effect of relative rib area T _s
	-	9.6 R _r + 0.28 (DFarwin et al. 1996a,b; Zuo and Darwin 1998,2000)
T_{b}	-	total bond force of a developed or spliced bar ; $T_{c} + T_{s}$
T_c	-	concrete contribution to total bond force, the bond force that would be
		developed without transverse reinforcement
T_s	-	steel contribution to total bond force, the additional bond strength
		provided by the transverse reinforcement
u	-	bond stress
u _b	-	bond strength of a bar confined by transverse reinforcement; $u_c + u_s$
u _c	-	average bond strength at failure of a bar not confined by transverse
		reinforcement
us	-	bond strength of a bar attributed to the confinement provided by the
		transverse reinforcement

CHAPTER 1

INTRODUCTION

1.1 Introduction

The overwhelming demand to reduce the country's dependency of unskilled foreign labor is one of the contributing factors of the government's drive to use Integrated Building System (IBS) for all government projects. Precast concrete system is one type of IBS system that is able to reduce manpower and increase construction speed. The use of precast concrete elements in building structures has increased gradually over the years. The latest generation of precast concrete structures had evolved into buildings of high specification. These types of buildings are able to meet high standard of architectural requirements in term of aesthetic values and good quality finishes, as well as fulfilling the building's structural needs.

In a precast concrete structure, the structural elements are fabricated off-site and delivered on site during erection. In this way, the construction process is expedited, less manpower on site required, less construction debris on site (e.g. formwork) and also

cleaner environment. The precast elements which are fabricated off-site are produced in a controlled factory environment resulting in high quality finish. It is also possible to use higher concrete grade or prestressed concrete to minimize the element sizes and maximizing the span. This will reduce the dead weight of the structure and therefore saving in the foundation.

1.2. Scope & Objectives

The objectives of this research paper are

- (i) To review various types of mechanical rebars couplers.
- (ii) To study the behavior of mechanical couplers as an alternative method for traditional reinforcing bars lapping in connection for precast concrete wall panels.
- (iii) To propose new mechanical couplers suitable for local market needs.

The scope of work will focus on studying the behavior of mechanical rebar couplers for precast wall panel connections and literature reviews on the introduction of structural ties in enhancing the robustness and stability of precast concrete building. Laboratory tests will also be carried out to evaluate new proposed mechanical couplers.

1.3 Problem statement

In normal practice, continuity between upper precast walls and lower precast walls are carried out by lapping the reinforcement bars. The lap length is normally between 30 and 40 the diameter of main bar depending on the concrete grade as recommended by BS code. The lapping length of bars often caused congestion in the connection and may create honeycomb or voids in concrete if precaution is not taken during concreting. In addition the extra lapping length also increases the reinforcing bars cost.

In theory, the use of mechanical couplers to replace the rebar lappings might be a logical solution because mechanical couplers do not occupied long lap length, easy to install and avoid bar congestion in the wall connection. In this research, we will study in depth the practical aspect as well as the engineering point of view on the role of mechanical couplers in providing continuity for structural reinforcing bars in precast wall panels. The cost of mechanical couplers available in the market is quite expansive, as such; experimental research will also be carried out on new proposed mechanical couplers that maybe able to fulfill market needs.

1.4 Expected finding

Toward the end of this research, we would be able to evaluate the viability of using mechanical couplers in precast wall panels and advise accordingly on its benefits and limitations. We would also be able to assess the performance of new proposed mechanical couplers based on results obtained from experiments carried out. Expected results from the experiments carried out will be relationships between Force – Deformation graphs and Stress – Strain curves.

CHAPTER 2

LITERATURE REVIEW

2.1 Introduction

In Malaysia, there are basically five common types of fully developed Industrialised Building Systems (IBS) which are the Precast Concrete System, Steel Formwork System, Steel Framing Systems, Prefabricated Timber Framing System and Block Work Systems. From the five types of IBS systems, Precast Concrete System and Steel Framing System are the two systems that can reduce construction time considerably because of their off site fabrication and on site installation. However, if we were to consider the two, it is clearly Precast Concrete System have an edge over the latter because of the raising cost of structural steel.

2.2 Structural Concept for Precast Concrete Systems

The structural concept for precast concrete systems is similar to cast-in-situ conventional reinforced concrete building system. The main difference between a precast building and a cast-in-situ concrete building is the structural continuity. In cast-in-situ building the structural continuity is intact as the building is being constructed because the joints between beams, slabs, columns and walls are cast in a monolithic manner. This is not so for precast concrete system where the structure components are prefabricated elsewhere and jointed together to form a structural system. The connections between these precast elements need to be rigid to form a bridging link to provide structural stability and safety to the precast system. A stable structural system will only be formed when the precast structural elements are jointed together, thus, it is important to consider in the design stage its stability and safety throughout all stages from construction to completion stage. The overall behavior of a precast building is very much dependent on its connections which should be able to transmit the vertical and horizontal loads to the structural elements, ductility to deformation, volume changes, durability, fire resistance, production.

In order to fully realize the full advantages of precast concrete, the structure should be conceived according to its specific design philosophy: long spans, appropriate stability concept, simple details and etc. It is also crucial to consider the possibilities, restrictions and advantages of precast concrete it's detailing, manufacture, transport, and erection and serviceability stages before completing a design in precast concrete.

2.3 Wall – Slab Frame Structural Systems

One of most common type of precast structural system is the wall – slab framing system. In the wall-slab frame system, the walls not only function as load bearing vertical elements but also act as lateral load resisting members. Vertical loads comes from the dead weight of the floor slabs, brick walls sitting on the slabs, floor finishes such as cement rendering, floor tiles, and imposed loads specified in the relevant code of practice. Wind loadings or notional loads formed the lateral loads acting on the building. An effective or efficient structural wall-slab system should have both cross walls and longitudinal walls to absorb horizontal forces. The walls are usually made up of concrete precast wall panels and the slabs are precast hollow-core slabs.

This type of structure is suitable for multi-storey hotels, retail units, hospitals, and offices. The structural vertical walls not only function as load bearing elements but are also used for partitioning.



Figure 2.1 – Wall – Slab Frame Precast System

2.4 **Progressive Collapse**

Progressive collapse can be defined as all or a large part of building that collapse is caused by a failure or small damage of a primary structural element in the building. This kind of catastrophic failure comes in the form of "domino effect" whereby a failure starting in a particular component rapidly propagates to other components precipitating a major or even a total collapse. The most famous landmark case of progressive collapse failure is the Ronan Point apartment collapse on 16 May 1968.

2.4.1 Ronan Point Apartment Collapse

On the morning of 16 May 1968, Mrs. Ivy Hodge, a tenant on the 18th floor of the 22-story Ronan Point apartment tower in Newham, east London, struck a match in her kitchen. The match set off a gas explosion that knocked out load-bearing precast concrete panels near the corner of the building. The loss of support at the 18th floor caused the floors above to collapse. The impact of these collapsing floors set off a chain reaction of collapses all the way to the ground. The ultimate result can be seen in Figure 1: the corner bay of the building has collapsed from top to bottom. Mrs. Hodge survived but four others died. While the failure of the Ronan Point structure was not one of the larger building disasters of recent years, it was particularly shocking in that the magnitude of the collapse was completely out of proportion to the triggering event. This type of sequential, one-thing-leading-to-another failure was labeled "progressive collapse" and the engineering community and public regulatory agencies resolved to change the practice of building design to prevent the recurrence of such tragedies. [2]



Figure 2.2 – Ronan Point Building after 16 May 1968 collapse [2]



Figure 2.3 – Schematic of Ronan Point Building collapse [4]

2.4.2 Provision in BS8110 on progressive collapse

Clause 2.2.2.2 of BS8110:Part1:1997 stipulates that the structure should be "Robust" and capable to resist accidental loads. In no circumstances a localized failure of a small part or single element of the structure would lead to the collapse of a bigger portion of the structure.

2	2	2	2	Ro	h	101	tn.	000	•
4.	- A	- 2	-4	KU	υı	เรเ	n	ess	ï

Structures should be planned and designed so that they are not unreasonably susceptible to the effects of accidents. In particular, situations should be avoided where damage to small areas of a structure or failure of single elements may lead to collapse of major parts of the structure.

Unreasonable susceptibility to the effects of accidents may generally be prevented if the following precautions are taken.

a) All buildings are capable of safely resisting the notional horizontal design ultimate load as given in 2.1.4.2 and is det each floor on people involtence on the

in **3.1.4.2** applied at each floor or roof level simultaneously.

b) All buildings are provided with effective horizontal ties (see 3.12.3):

1) around the periphery;

2) internally;

3) to columns and walls.

c) The layout of building is checked to identify any key elements the failure of which would cause the collapse of more than a limited portion close to the element in question. Where such elements are identified and the layout cannot be revised to avoid them, the design should take their importance into account. Recommendations for the design of key elements are given in **2.6** of BS 8110-2:1985. d) Buildings are detailed so that any vertical load-bearing element other than a key element can be removed without causing the collapse of more than a limited portion close to the element in question. This is generally achieved by the provision of vertical ties in accordance with **3.12.3** in addition to satisfying a), b) and c) above. There may, however, be cases where it is inappropriate or impossible to provide effective vertical ties in all or some of the vertical load-bearing elements. Where this occurs, each such element should be considered to be removed in turn and elements normally supported by the element in question designed to "bridge" the gap in accordance with the provisions of **2.6** of BS 8110-2:1985.

Figure 2.4 – Extracts from BS8110: Part 1: 1997 [1]

To minimize the effects of progressive collapse of a building, BS codes recommended three mitigation measures as follows:

(i) The structure should be designed to resist the notional horizontal design ultimate load which acts at the same instant applied at each floor and roof level. Notional load equals 1.5% of the characteristic dead weight of the structure between mid height of the storey below and either mid height of the storey above or roof surface. (Clause 3.1.4.2: BS8110)

- (ii) The building should be provided with horizontal and vertical ties around the fringe or outer boundary, internally and to columns and walls. In cast-in-situ concrete buildings, the structural beams which are connected monolithic to the columns act as horizontal and vertical ties for the building. This is not the case for precast concrete building where all the precast elements are jointed together to form a structural system, therefore, to ensure structural continuity the provision of vertical and horizontal ties is important.
- (iii) The structure framing should avoid any key elements in the building. Key elements refer to the important of a particular structural member which when removed will lead to a large portion of the building to collapse. However, if this cannot be avoided, these elements should be designed with a higher factor of safety.



Figure 2.5 – Location of ties in precast skeletal structure [2]